

READY-BILT™

FACTORY PRE-ASSEMBLED WALK-INS



FROM

MB MASTER-BILT®
Refrigeration Solutions

Ready-Bilt walk-ins are completely pre-assembled at the factory and ready to set in place at the job site. Structures arrive at the site typically on a gooseneck truck and, depending on size and customer preference, lifted into place by crane, boom-lift or forklift. No field installation is necessary. The refrigeration system(s) is already installed and the entire walk-in is fully tested before shipping. All you have to do is provide electricity for the single source hook-up (one per refrigeration system). Each Ready-Bilt walk-in is UL-listed as an entire package, not just for individual components, facilitating electrical inspections.

MB MASTER-BILT[®]

READY-BILT[™]

STANDARD FEATURES:

- Single or double compartment models available
- Available in a variety of lengths and widths
- Cam-locking four-inch thick foamed-in-place polyurethane panels
- Interior and exterior panel finish of 26 gauge acrylic-coated stucco galvanized steel
- Panels and doors are designed and certified for use in walk-in cooler and freezer applications. All panels meet or surpass these minimum R-values required by the DOE:
 - Cooler walls, ceilings and doors: R-25
 - Freezer walls, ceilings and doors: R-32
 - Freezer floors: R-28
- ColdSeal Max[™] door with welded, structural anodized aluminum frame, heavy-duty wide strap hinges and heavy-duty door closer
- Choice of 26" x 78", 30" x 78" or 36" x 78" door sizes
- Door energy consumption (kWh/day):

36" x 78" door	26" x 78" door	30" x 78" door
Coolers: 2.77	Coolers: 2.49	Coolers: 2.60
Freezers: 7.79	Freezers: 7.01	Freezers: 7.33

- Digital thermometer
- Door drip guard
- NSF-listed .080 textured finish aluminum floor for added slip-and-fall protection.
- Bands of aluminum treadplate for finishing trim around top and bottom of walk-in
- Weather-proof membrane roof to keep rain from collecting against an adjacent building
- Pre-installed refrigeration system(s) using either a remote M-Series condensing unit or a PRS-2 series packaged system depending on application
- Durable hard copper soldered piping on M-Series refrigeration systems
- LED lighting
- A warranty that covers parts and labor for one year, the compressor for one year (optional extended four year warranty available) and walk-in panels for 15 years

OPTIONS INCLUDE:

- Door kickplates
- Interior and exterior ramps
- Interior and exterior finish options include all those found in our custom Bilt2Spec[™] walk-ins
- Ceiling mounted LED lighting
- MBWA-1 digital alarm and light management system
- Master Controller Reverse Cycle Defrost system for M-Series refrigeration systems



Heavy-duty door hinges are field adjustable to compensate for door settling. The cam-lift feature on all hinges together with a spring-loaded bottom hinge help ensure doors close completely.



Ready-Bilt walk-ins are equipped with standard LED lighting which is designed to reduce electrical usage by up to 85% and last up to 50,000 hours vs. 1000 hours for incandescent bulbs. Fixtures are mounted at the top of the interior door to avoid blockage from shelves and stored items for full interior illumination.



A digital thermometer/light switch is conveniently integrated into one component. The waterproof "elbow-engaged" illuminated light switch allows operators to turn on the light easily, even when their hands are full.



908 Highway 15 North • New Albany, MS 38652
800-647-1284 • FAX: 800-232-3966
www.master-bilt.com

